SANITARY DIVISION.

Dated 17th March 1910.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Sanitary Division, up to 12 noon of 2nd April 1910, for the extension of Shimoga Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1912.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's office at Bangalore, between the hours of 11 A.M. and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one thousand in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for the extension of Shimoga Town" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Sanitary Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The approximate cost of work to be done by end of June 1910 is Rs. 8,000.

Description of work	Per	Quantity
Opening out roads and lanes—		
Earthwork, cutting	C. yd.	26,978
Embankment	„	7,865
Collection of metal from boulders, from 1" to 2" Ring ...	„	5,132
Collection of gravel	„	2,787
Spreading metal including watering and tamping	„	9,094
Do gravel do	„	4,437
Spreading sand including collection	„	302½
Side drains, both sides	100 R. ft.	39,726
Forming road	S. yd.	128,070
One mile lead for metal	C. yd.	3,575
Half a mile lead for gravel	„	694
Blasting rock	L. S.	250
Turfing slopes	L. S. Sqr.	4·00
Constructing tunnels—		
Earthwork, excavation	C. yd.	3,082
Dry stone packing	„	4
Pointing with chunam	S. yd.	123·65
Covering slabs 6"	S. ft.	9,444
Rough stone in mortar	C. ft.	48,381
Burnt brick in mortar	„	6,534
Coping slabs 3" to 4"	S. ft.	3,708
Chunam plastering	Sqr.	143·07
Rough stone apron	C. yd.	588

J. BHORE,
Sanitary Engineer.

FOR SALE.

About 20 tons of unserviceable iron and steel tools are available for sale at Marikanave, consisting of—

Pickaxes weighing	6,000	lbs.
Momties „	5,000	„
Butt-hammers, stone-breaking hammers and sledge hammers, weighing	12,000	„
Steel jumpers and crow-bars from 1 to 3 feet in length, weighing	10,000	„
Steel bits, chisels, felling axes, tampers and miscellaneous scrap, weighing	12,000	„

Tenders are invited for the purchase of the above.

Apply—

H. D. RICE,
Executive Engineer, Marikanave Division.